SITE STRATEGIES

Field-Level Insight Report

Sample report: what is working, what is broken, what needs attention

SAMPLE DOCUMENT - All company, project, and personnel names are fictional, and all figures are illustrative. This sample shows what a client receives; it is not a report on a real project.

Prepared for	Management, Northline Civil Ltd. (fictional example)
Project	Harbourview Subdivision, Stage 2 - storm sewer and road servicing, Ontario
Prepared by	Site Strategies - Neil Beaven, Founder
Basis	One full-day site walkthrough, crew conversations, and review of the prior two weeks of field records

1. Executive summary

The crew installs good pipe. The job is losing time before the pipe ever gets in the ground. Over the sample week the crew installed 60 metres against a plan of 100 metres. The gap is not install speed: when the trench is open and material is on site, the crew installs at plan rate. The gap is waiting time, 11.5 standby hours in five days, plus a lookahead that no longer matches deliveries and field records too thin to bill or defend a change.

- What is working: install quality on inspected sections, material staging and housekeeping, survey control current, foreman-to-crew communication.
- What is broken: the two-week lookahead has not been updated in 9 days, so the crew is working to a plan that deliveries have already outrun.
- What needs attention now: one changed condition (an unmarked lateral) was worked around without written notice, leaving 2.5 hours plus vac truck time with no change record. That cost is at risk.
- Bottom line: at the sample-week pace, the remaining 300 metres takes 25 working days instead of the planned 15. That is 10 working days behind if nothing changes.

© Site Strategies. All rights reserved. | SAMPLE - Fictional data for illustration only.

2. How this was assessed

One full day on site: walked the active workface, watched a full install cycle, and spoke with the foreman, topman, pipelayer, and operator. Records reviewed: daily reports, the current two-week lookahead, delivery tickets, and the change log for the prior two weeks.

What this report does not cover: design adequacy, survey accuracy beyond control being current, the company books, or subcontractor pricing. Findings are limited to what the walkthrough and the records show.

3. Production snapshot - sample week

Planned production is 20 metres per day. The table below is taken from the week's daily reports, with standby reasons as recorded by the foreman.

Day	Planned (m)	Actual (m)	Standby (hours)	Main standby reason
Mon	20	14	3	Inspection wait
Tue	20	10	2	Material delivery late
Wed	20	16	2.5	Unmarked lateral - utility conflict
Thu	20	8	2	Equipment breakdown
Fri	20	12	2	Inspection wait
Total	100	60	11.5	40 metres behind plan

Remaining pipe is 300 metres. At the planned 20 metres per day that is 15 working days. At the sample-week actual of 12 metres per day it is 25 working days. The difference is 10 working days.

4. Findings

Findings are numbered for reference in discussion. Priority means: HIGH - fix this week; MEDIUM - fix this phase.

F-01 - Lookahead out of date (HIGH)

Observation: the two-week lookahead posted in the site trailer is 9 days old. Two material deliveries on it have already slipped, and the crew learned of both slips on the day, not in

© Site Strategies. All rights reserved. | SAMPLE - Fictional data for illustration only.

advance. Evidence: lookahead dated 9 days before the walkthrough; delivery tickets showing revised dates. Impact: the crew cannot sequence ahead, so every slip becomes standby time.

F-02 - Production gap is waiting time, not install speed (HIGH)

Observation: 60 metres installed against 100 planned, with 11.5 standby hours. When the trench is open and material is staged, install pace matches plan. Evidence: daily reports for the sample week (see Section 3). Impact: 10 working days behind on the remaining 300 metres if the pace holds.

F-03 - Daily records too thin to bill or defend (HIGH)

Observation: three of the five daily reports in the sample week record no installed quantities, and two record standby time with no reason. Evidence: daily reports, sample week. Impact: quantities reach billing 4 to 6 days late, and standby time cannot be tied to a cause, a direction, or a change.

F-04 - Changed condition worked without written notice (HIGH)

Observation: an unmarked lateral forced a change in sequence on Wednesday. The crew worked around it, but no written notice was issued and no change record was opened. The 2.5 hours plus vac truck time sit outside any claim. Evidence: foreman account, Wednesday daily report, no entry in the change log. Impact: that cost is recoverable only if notice and records are created now; every day without them weakens it.

F-05 - Quantities handoff has no owner or deadline (MEDIUM)

Observation: the foreman collects quantities, but there is no set handoff to the office and no confirmation back. Quantities arrive 4 to 6 days after the work. Evidence: billing dates vs install dates, sample period. Impact: billing lags, and quantity disputes surface weeks after the work is covered.

F-06 - Safety and quality paperwork is generic (MEDIUM)

Observation: job hazard assessments on file are generic rather than task-specific for this week’s trench work, and one trench inspection sign-off is missing from the file before backfill. The work itself met spec on re-check. Evidence: JHA file, inspection file. Impact: low today, but the file would not defend the work if an incident or a dispute arose.

5. What is working

- Install quality: no rework on inspected sections in the sample period.
- Material staging and housekeeping: laydown is organized and access is kept clear.
- Survey control: current, and the crew trusts it.

© Site Strategies. All rights reserved. | SAMPLE - Fictional data for illustration only.

- Crew communication: foreman-to-crew direction is clear; the crew raises problems early when asked.

6. What this means for management

- Schedule: 10 working days of exposure on the remaining pipe at current pace.
- Cost: 11.5 standby hours in one week, plus one unbilled change event. Both are controllable.
- Risk: the missing written notice (F-04) is the only finding that gets worse with time. It should be dealt with first.
- No finding here requires more crew or different equipment. The fixes are about planning, records, and notice discipline.

Appendix A - Walkthrough checklist used

This is the assessment structure behind the report, so the same walkthrough can be repeated on any job. It is also the tool used to audit: each area is checked on site and against the records before any finding is written.

Area	Checked on site	Checked in records
Planning	Lookahead posted and current; crew knows tomorrow's work	Lookahead updates, delivery dates, permit and locate status
Production	Install cycle watched; standby observed and timed	Planned vs actual quantities, standby reasons
Commercial controls	Change conditions flagged on the day	Notices issued, change log, tickets signed
Roles and handoffs	Who owns quantities, records, and escalation	Handoff timing, billing lag
Safety and quality	Task-specific JHAs, inspection sign-offs	JHA file, inspection file, deficiency close-out

© Site Strategies. All rights reserved. | SAMPLE - Fictional data for illustration only.